## PROPANE HEATER SCHEDULE

| TAG | MANUFACTURER | MODEL | LOCATION | HEATING | | | DIMENSIONS | | | THERMOSTAT | SHIPPING WEIGHT (lbs) |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | INPUT CAPACITY (BTU/Hr) | OUTPUT CAPACITY (BTU/hr) | THERMAL EFFIENCY | WIDTH (in) | DEPTH (in) | HEIGHT (in) | | |
| H-1, H-2 | WILLIAMS COMFORT PRODUCTS | 1403821 | LIVING ROOM & BEDROOM | 14,000 | 9,800 | 70% | 18 | 7 | 26 | MILLIVOLT | 56 |

NOTES & REMARKS:
· PROVIDE WITH VENT-CAP GUARD
· PROVIDE THIN-WALL COLLAR KIT IF EXTERIOR WALL IS 5" OR LESS

## EXHAUST FAN SCHEDULE

| TAG | AREA SERVICED | MANUF. | MODEL | TYPE | WEIGHT (KG/LBS) | FLOW (LPS/CFM) | E. SP (mm.W.C./ IN.WC) | FAN | | | | REMARKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | VOLTS | FLA | KW/HP | RPM | |
| EF-1 | WASHROOM | GREENHECK | SP-A50 | DIRECT DRIVE | 5/12 | 35/75 | 6.35/0.25 | 115/1/60 | ~0.5 | 0.03/- | 790 | -CEILING MOUNTED EXHAUST FAN<br>-PROVIDE WITH 1 FUNCTION SWITCH, DEHUMIDISTAT, ROUND DUCT CONNECTOR AND VIBRATION ISOLATION KIT, ROOF (OR SIDEWALL) TERMINATION KIT) |

## KITCHEN & PLUMBING EQUIPMENT SCHEDULE

| ITEM NO. | EQUIPMENT DESCRIPTION | QTY. | PLUMBING | | | REMARKS |
|---|---|---|---|---|---|---|
| | | | HOT | COLD | DRAIN | |
| | | | | | | |
| WC-1 | WATER CLOSET | 1 | | 1/2" | 3" | |
| LAV-1 | LAVATORY | 1 | 1/2" | 1/2" | 1-1/4" | |
| SH-1 | SHOWER HEAD | 1 | 1/2" | 1/2" | 1-1/2" | |
| DW-1 | DISHWASHER | 1 | | 1/2" | 1-1/2" | |

## DRAWING LIST

| DWG NO. | DESCRIPTION |
|---|---|
| M-1 | MECHANICAL SPECIFICATIONS |
| M-1.1 | MECHANICAL SPECIFICATIONS CONT'D |
| M-1.2 | SCHEDULES |
| M-2 | PLUMBING AND DRAINAGE |
| M-3 | HVAC |

STEEL CANADA ROOFING & SIDING LTD.
360 TRAVERS BLVD. EAST, MISSISSAUGA, ON, L4Z 2E5
www.steelcanadaroofing.com

entrust ENGINEERING INC
353-640 THE EAST MALL, TORONTO, M9B 4J7 0:647-230-7202

ISSUES:

| NO. | BY | DATE | ISSUED FOR |
|---|---|---|---|
| 2 | EOF | 5.MAY.2021 | REVISION TO PROPANE |
| 1 | EOF | 23.APR.2021 | CLIENT REVIEW |

PROFESSIONAL SEAL:

PREPARED FOR:

STEEL CANADA ROOFING & SIDING
16'x40' SHIPPING CONTAINER MODULAR UNIT
TORONTO, ON

DRAWING TITLE:
SCHEDULES

PROJ.NUMBER: 21059
SCALE: AS SHOWN
DRAWN BY: ND
PLOT DATE & TIME:

SHEET NUMBER:
M-1.2